

PR8431407: REQUEST FOR QUOTATION FOR PROVISION OF MAINTENANCE AND WEAPONS RANGE UPGRADES AT THE DEPARTMENT OF STATE RANGE LOCATED IN MOGADISHU, SOMALIA

Date: July 30, 2019

SUBJECT: PR8431407: REQUEST FOR QUOTATION FOR RANGE MAINTENANCE AND UPGRADES IN SOMALIA

The UNITED STATES MISSION TO SOMALIA, invites you to submit a request for proposal for:

Requisition Title: - PR8431407: REQUEST FOR QUOTATION FOR RANGE MAINTENANCE AND UPGRADES IN SOMALIA

STATEMENT OF WORK (SOW)

1. Contractor shall provide and install upgrades to the existing container on site
 - a. Treat rust, prime surface and paint with two coats enamel to external surfaces only.
 - b. Relocate existing container to butt up to Hesco to accommodate new container to be supplied by client. New container to be collected and put into position by DFS contractor
 - c. Erect new 2.0m x 6.0m timber deck to front of existing container.
 - d. Erect new 1.0m x 6.8m timber deck to end of existing container.
 - e. Erect new mono pitch roof covering over two containers and new decks
 - f. New exposed timber to be varnished three coats.
 - g. Construct new timber working surface to front of container 6.0m x 0.9m x 0.6m high
2. Contractor shall provide maintenance to the existing gate.
 - a. Treat rust prepare surface and repaint three coats enamel
 - b. Ensure gates are in good working order and functional
3. Contractor shall provide and install a new stand alone roof cover
 - a. Build a new 5.0m x 8.0m x 3.0m high open sided roof on timber support posts.
 - b. Cast new concrete surface bed wood floated and steel troweled 100mm thick beneath new open roof.
 - c.
4. Contractor shall provide, install and repair Hesco barriers that have been identified.
5. Contractor shall provide and install a Bullet Catcher as the backstop of the range.
 - a. Construct new bullet catcher to front of firing range as per discussion with Rick and Gerrit

- b. Provide 8m x 3.0m high Hesco to right of firing range
 - c. Remove +/- 300mm of soil behind targets to remove lead and replace with new
 - d. Build and install a timber retaining box at foot of sand slope at target area
6. Contractor shall provide ground leveling and clean up
- a. Pull out all foliage and level ground
 - b. Grade existing soil and provide fall to prevent standing water
7. Contractor shall provide 2 new shade ports with the dimensions and locations as listed below
- a. New shades to be 4.0m x 12.0m long, on 165mm x 70mm frame with wire support at 1.0m centers. Support posts to be 4.0m apart
 - b. Shade ports are to be installed as follows:
 - 1. One at the ten meter mark
 - 2. One at the 25 foot mark

The U.S. Government intends to award a Purchase Order to a responsible company submitting an acceptable quotation at a reasonable price. The RFQ does not commit the American Embassy to make any award. The Embassy may cancel this RFQ or any part of it.

Your proposal must be submitted on email attachments addressed to:

To the Contracting Officer, American Embassy, through NairobiGSO-bids@state.gov and copy AbdilatifMS@state.gov; **on or before August 14, 2019.**